



Delivering What matters 2009 - 12

Council Priorities

- Affordable Housing
- Better Skills & Education for employment
- <u>Carbon Emissions & energy use reduced</u>






Carbon Priority – Aims & Objectives

- Reduce carbon emissions and energy use, optimise energy efficiency and use renewable energy where possible across the Wrexham County Borough area.
- Aspirational targets 50% reduction by 2015 and 70% reduction by 2020.



The context - Social Housing CO₂ Footprint





Further Pressure....National Drivers

- UK Gov't committed to reduce CO2 emissions by 80% by 2050
- 27% of UK's CO2 emissions come from Housing
- But... 80% of homes that will exist in 2050 have already been built
- **332,000 (26%)** of households in Wales are in fuel poverty (2008)
- By 2025 WAG aims to generate twice as much renewable energy






What are Photovoltaic (PV) solar panels?

A - PV panels (on south facing roofs) will capture and convert the energy from the sun into electrical energy (direct current).

B – An invertor will convert the direct current into alternating current, to enable it to be used to power household appliances.

C – A generation meter will record how much electricity the PV panels have generated.

D – Excess electricity will be exported back to the national grid.





Feed in Tariffs (FIT)

- New Government backed scheme to promote uptake of small scale renewable and carbon technologies (Microgeneration)
- Makes low carbon electricity generation financially viable by attaching an income to electricity generated and used and/or exported to the grid
- Applies to photovoltaic panels (PV), small scale wind turbines and micro CHP units
- Paid by Utility Companies NOT Government
- FITs payment designed to exceed cost of loan repayments for installation cost
- Tariffs linked to Retail Price Index
- Only installations by MCS Registered Installers using MCS Certified Products are eligible



Project overview

- Installation of PV systems onto 3000 Council owned domestic and 13 non domestic buildings.
- Total Cost approx £28m
- Net surplus income approx £25m
- Installation complete by March 2013 (or sooner)
- 2011/12 and 2012/13 1500 installations per year
- **30** installs per week (60?)
- 6 installs per day (12?)





The Project - Non Domestic Buildings

- A minimum of 13 Council owned non domestic properties will also have PV installed.
- Ranging from schools, Council offices, Tennis centre etc....
- Additional bonus... Council benefits from reduced energy bills.
- Cost for this element of the project approx £3.4m, with a net income of £3m over 25 years
- 3% reduction in carbon footprint








The Project – Domestic Buildings

- Wrexham has 11,500
 Council owned domestic properties.
- Desk top survey completed to establish number of properties that are predominantly South facing.
- Findings..... 4500 properties are suitable.





The Project in more detail

- On Site surveys now complete on 4500 suitable properties identified via desk top survey. This includes assessment of:
 - Condition of roof
 - Size of system that can be fitted
 - Tree coverage
 - Chimney stacks
 - Other obstacles
- Full surveys including asbestos and structural stability of properties will be carried out prior to installation.









The Project in more detail – on site matrix

Roof Length	Roof Height	No of Panels	Size of system	FIT/Year	Import savings
8	2	9	1.5kw	£520	£82
7	3	12	2.2kw	£733	£113
8	3	14	2.5kw	£856	£135
8	4	16	2.8kw	£925	£146
8	5	21	3.8kw	£1283	£202




Pilot Properties

- Test feasibility of project and mitigate risks
- The process involved consulting with tenants, structural and asbestos surveys, procuring panels, arrange installation, draw up contracts, monitor productivity
- Outlying area of the Borough
- 5 properties to be completed by end March 2011









The Benefits

WIN

WIN

WIN









A further potential benefit.....

- •Opportunity to upskill internal electricians to MCS standard, working with SHARP & Yale College
- Further opportunity to offer training courses to local electrical contractors
- •Sell2Wales speculative market sounding notice – 40+ companies expressed interest
- •PV awareness raising event 24th November
- •EST 0% loans to encourage local contractors to gain MCS accreditation

Training & Development









The 5 Big Issues

Delivery options



Timescales



Risks



Procurement



Equalities






Project Delivery Options



1.Internally fund the design, supply and installation



OR

2. Engage external company to fund the design, supply and installation



Project Delivery Options

Benefits of financing & managing the project internally

- •Full control
- •Ability to **claim all of the FIT** and maximise income generation for the authority
- Not reliant on external company
- •Council has **full ownership** of all assets (roof and equipment)

<u>Limitations of financing & managing the project</u> internally

- Significant financial borrowing required
- •Insufficient internal capacity to manage project
- •Insufficient expertise (legal/procurement) to deliver project
- •Reduced likelihood of delivering project on time

Benefits of engaging an external company to finance & manage the project

- •No financial commitment required from the Council
- Reduced risks (risks sit with company)
- Limited internal resources required
- •More experience in this field
- Potential quicker route to commence installations

<u>Limitations of engaging an external company</u> to finance & manage the project

- •FIT is claimed by external provider missed opportunity.
- •Success of the **project is reliant on external provider** what if they can't deliver?
- Loss of control
- •Council will still incur some resource costs admin etc.
- •External provider will complicate relationship between tenant and utility provider.
- •Issues of ownership of assets



Procurement Cont'd

Option 1





Benefits

Full control, incorporate specific requirements, not reliant on others

Weaknesses

Few examples of this working well, time consuming, resource intensive, costly, require considerable support



Procurement Cont'd

Option 2

Use alternative Procurement framework



Benefits

Expedience, reduced internal burden, OJEU compliant,

Weaknesses

Little evidence of any current successful frameworks, dependant on framework operator.



Timescales



"Fast-track review to be launched into large scale solar installations"

"Solar projects below 50 kW and all tariff changes until April 2012 "

"FIT review to be complete by end of March 2012 at earliest"

"Large scale solar installations the FITs weren't anticipated under the scheme"




"Window of opportunity"



route

Project Timeline





Equalities

Some 8000 tenants will not have PV installed!!

<u>Is this</u> <u>fair?</u>



How can this be overcome?

- Income generated can be recycled back into the Housing Revenue Account
- Consider other forms of renewables for those not having PV installed (air source heat pumps)
- Consider exploiting the RHI
- Install PV on East, West, facing properties



Project Risks



High Risks



- Delivery by March 2013 (or before) for maximum benefit from FITs
- Tenant & Member concern about equity of distribution
- Requires substantial funding approx £25 million
- Procurement UK Government change the FITs



Project Risks



Medium Risks



- Shortage of MCS accredited supply and installers
- Shortage of equipment
- FIT 'pot of money' runs out!
- Financial, technical, legal due diligence
- Condition of properties (structurally & asbestos)



Project Risks



Low Risks



- Equipment becomes superseded or is unreliable
- Internal capacity and expertise to deliver
- Property shading/obstacles
- Housing Stock Transfer & Right to buy applications
- Automatic Meters
- Planning permissions
- Vandalism



Future Direction of project

Vast number of opportunities to expand and build on the project, if successful. Initial thoughts range from:

- Collaboration with other LA's and/or Public Sector Organisations
- Offer as a chargeable service to owner occupiers across Wrexham
- Install PV onto Non South Facing properties
- Consider installations onto Community centres etc





Next steps

- 4 more pilot installations to be completed by March 2011
- Continue on site surveys to firm up potential properties and non domestic buildings that are suitable
- Firm up financial modelling and technical specification
- Manage expectations
- Consultation & Engagement

